

THOMAS MANUFACTURING **PTY LTD** **MOBILE** **BATCHING PLANT**



2025 TOP OF THE RANGE BATCHING PLANT BULKA BAG FILL SYSTEM

GENERAL DETAILS AND SPECIFICATIONS

- ✓ New 9 metre x 600mm 35-degree troughed conveyor running at 1.25 metres per second.
- ✓ New 6 cubic metre loading hopper with fold up hungry boards.
- ✓ New 5-digit readout 75mm high on weighing system-24 volt.
- ✓ New 20 tonne capacity shear beam load cell system.
- ✓ New Rinstrum plug and play system.
- ✓ New Air operated open/close clamshell doors on hopper.
- ✓ New SEW KT67 gearbox with 4kW 3 phase motor on conveyor.
- ✓ New 2.5 cubic metre cement hopper with air slide and bag spike.
- ✓ New auger from air slide on cement hopper to top of conveyor for cement powder discharge.
- ✓ New SEW FT77 gearbox with 9.2kW 3 phase motor on auger.
- ✓ New air operated butterfly valve with controller.
- ✓ New Peerless HQE5.5VSHP-110 5.5HP direct driven variable speed high pressure screw compressor.
- ✓ New access ladder and platform to cement hopper.
- ✓ New THOMAS troughing frames and rollers.
- ✓ New Tail drum.
- ✓ New Head drum hot vulcanised.
- ✓ New Lowara stainless steel 50mm outlet high volume water pump, 3phase motor 3kw.
- ✓ New Fully automatic water flowmeter.
- ✓ New Land cruiser rims and tyres.
- ✓ New two sets 28 tonne wind down trailer legs.
- ✓ New 6 tonne tow ring.
- ✓ New retractable water hose.
- ✓ New retractable air hose.
- ✓ New spit water high pressure wash down system.
- ✓ New camera and screen to view clam shell and conveyor capacity.
- ✓ New operator Kings retractable shelter.
- ✓ Fully sandblasted and powdercoated. Colours to be advised.
- ✓ New head chute to reduce spillage.
- ✓ New electrical control box containing all stop / start control for conveyor, air compressor, water pump and auger.

**PRICE FOR THE ABOVE UNIT
\$245,700 + GST.**

**TO ADD A VIKING 44KVA 3 PHASE GENERATOR TO THIS PLANT
WOULD BE AN ADDITIONAL \$27,236 + GST.**

**TO ADD AN ISO FILL SYSTEM TO THIS PLANT WITH A
DUSTCOTECH SELF CLEANING FILTER SYSTEM WITH
HANDRAILS, KICK RAILS AROUND THE TOP, A MANHOLE
AND CAGED LADDER WOULD BE ADDITIONAL
\$38,200 + GST.**

**TO ADD THOMAS INTEGRATED BATCH CONTROL SYSTEM
WOULD BE AN ADDITIONAL \$16,700 + GST.**

**TO ADD ADDITIVES TO THIS PLANT WOULD BE AN
ADDITIONAL \$5,260 + GST PER LINE.**

**40% DEPOSIT IS REQUIRED TO COMMENCE WORK.
BALANCE IS REQUIRED BEFORE DESPATCH FROM OUR
DALBY YARD.**

Deposits can be made via Direct Deposit into our account:

Account Name: Thomas Manufacturing Pty Ltd

BSB: 034 177

Account #: 18 3514

ABN: 48 109 689 894

Thank you for your interest.

